BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 57

Name of Work:-Improvements of drains and construction of culverts Vidyanikethan School road, Attur layout in Attur ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri JAYANTH T GOWDA	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift no to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138,PWD SR 2014-15)	Cum	121.28	70.00	Rupees seventy only
2	Removing B.S slab of drain and stacking	Sqm	450.45	50.00	Rupees fifty only
3	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	450.45	70.00	Rupees seventy only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	341.55	620.00	Rupees six hundred twenty only
5	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	16.64	240.00	Rupees two hundred forty only
6	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	137.12	60.00	Rupees sixty only
7	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no4.3,Page no12,PWD SR 2014-15)	Cum	0.90	4750.00	Rupees four thousand seven hundred fifty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri .JAYANTH T GOWDA	
				Rate	Rate in Words
8	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work(pwd sr2014-15,p.no13,sno4.11)	Cum	4.08	5850.00	Rupees five thousand eight hundred fifty only
9	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr2014-15,p.no17,s.no4.46)	Qnt	4.08	7870.00	Rupees seven thousand eight hundred seventy only
10	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecification. Specification no.KBS 4.6.2(pwd sr2014-15,p.no15/4.31)	Sqm	18.00	250.00	Rupees two hundred fifty only
11	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. (Page No. 144 & Item No. 19.60)	Cum	81.00	200.00	Rupees two hundred only
12	KSRRB M1400-14.1. Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density. Material Using Scrining Crushable Type such as Moorum or Gravel Grading - II (Manual) Clause : 404 (P.143/I.20.15.3 PWD SR - 2014-15).	Cum	40.50	1590.00	Rupees one thousand five hundred ninety only
13	KSRRB M1400-14.2. Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density. Material Using Scrining Crushable Type such as Moorum or Gravel Grading - III (Manual) Clause : 404 (P.143/I.20.15.3 PWD SR - 2014-15).	Cum	30.38	1390.00	Rupees one thousand three hundred ninety only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri JAYANTH T GOWDA	
				Rate	Rate in Words
14	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Sqm	60.00	978.00	Rupees nine hundred seventy eight only
15	KSRB 5-15: Providing and constructing Non load bearing wall with cement concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.28)	Sqm	60.00	710.00	Rupees seven hundred ten only
16	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs,with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications.Specification no4.1,4.2 (Page.12 & Item No. 4.6)	Cum	12.00	5250.00	Rupees five thousand two hundred fifty only
17	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	270.00	1230.00	Rupees one thousand two hundred thirty only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.